

**SURVEY & REMONUMENTATION**

FEB 14 1997

COMMISSION

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 MAR 20 AM 8:55  
 REG. OF DEEDS  
*Lucy Stand*

For corners in

**KENT COUNTY**

(County)

Located In:

Corner Code #

- |                                    |  |             |
|------------------------------------|--|-------------|
| 1. Public Land Survey              | T <u>8N</u> R <u>11W</u>               | <u>D-11</u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |

**9049**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 17, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11			●									
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-11	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron
	1983	LCRC #3310	Glaza	1/2" Iron
	1983	LCRC #3526	Stadt	Set Kent County Monument
	1994	LCRC #6913	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/7/96  
 CHAIRMAN *Russel E. Stadt*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russel E. Stadt on 9/7/83 and was recorded per LCRC #3526.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Russel E. Stadt in place of the 1/2" Iron Pipe he found. Said Iron Pipe checks with Kent Co. Wit. and LCRC #3310.

<u>LCRC #3526</u>		<u>LCRC #6913</u>	
Nail/tag 24" Oak	North 29.30'	Nail/tag 30" oak	N00°E 29.30'
Nail/tag 28" Tw. Oak	S88°E 51.51'	Nail/tag 30" Tw. Oak	S88°E 51.55'
Nail/tag P. Pole	S56°E 85.42'	Nail/tag P. Pole	S56°E 85.47'
Nail/tag 10" Sassafras	West 22.51'	Nail/tag 12" Sassafras	S90°W 22.52'
Nail/tag 20" W. Cherry	N15°W 11.90'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11 Standard Kent County Monument		
Nail & KC Remon. tag E. side 30" oak	N00°E	29.30'
Nail & KC Remon. tag N. side 30" Tw. Oak	S88°E	51.55'
Nail & KC Remon. tag SW side P. Pole	S56°E	85.47'
Nail & KC Remon. tag S. side 12" Sassafras	S90°W	22.52'
Set Nail & KC Remon. tag W. side fence post	S00°E	9.72'



Signed by *Kirk Breitels*  
 Surveyor's Michigan License No. 30077

Date 2/6/96