

**SURVEY & REMONUMENTATION**

FEB 14 1987

**KENT COUNTY REMONUMENTATION**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- |                                    |         |                          |            |
|------------------------------------|---------|--------------------------|------------|
| 1. Public Land Survey              |         | T <u>8N</u> R <u>11W</u> | <u>E-2</u> |
|                                    |         | T _____ R _____          | _____      |
|                                    |         | T _____ R _____          | _____      |
|                                    |         | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ | T _____ R _____          | _____      |
|                                    | S _____ | T _____ R _____          | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ | T _____ R _____          | _____      |
|                                    | S _____ | T _____ R _____          | _____      |

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 MAR 20 AM 8:55  
 REG. OF DEEDS  
*Luc Standa*

**9051**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 26, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5	●	4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-2	1837	GLO	Whitcomb	Set Post
		Kent Co. Wit.		Fence E & W
	1972	LCRC #183	Spicer	1" Iron
	1981	LCRC #2268	Bueche	Set Kent County Monument
	1994	LCRC #6915	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/7/96  
 CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10/16/81 and was recorded per LCRC #2268.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #183.

<u>LCRC #2268</u>		<u>LCRC #6915</u>	
Nail/tag P. Pole	S45°E 117.25'	Nail/tag P. Pole	S45°E 118.40'
Nail/tag 8" Poplar	N90°E 90.23'	Nail/tag 12" Poplar	N90°E 90.37'
Nail/tag 16" Maple	N75°E 80.14'	Nail/tag 18" Maple	N75°E 80.16'
Nail/tag 12" Maple	N65°E 138.95'	Nail/tag 12" Maple	N65°E 138.95'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-2 Standard Kent County Monument in swamp

Nail & KC Remon. tag NE side S'y P. Pole	S45°E	118.40'
Nail & KC Remon. tag S. side 12" Poplar	N90°E	90.37'
Nail & KC Remon. tag S. side 18" Maple	N75°E	80.16'
Nail & KC Remon. tag SE side 12" Maple	N65°E	138.95'



Signed by *Kirk Breitels*  
 Surveyor's Michigan License No. 30077

Date 2/6/96