

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>8N</u> R <u>11W</u> | <u>E-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 MAR 20 AM 8:56
 REG. OF DEEDS
W. J. [Signature]

9053

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN *[Signature]*

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8	●	9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|-----|------|---------------|-----------|--------------------------------------|
| E-4 | 1837 | GLO | Whitcomb | Set Post |
| | 1964 | Kent Co. Wit. | | 1/2" Iron |
| | 1973 | LCRC #611 | VanKooten | Bolt Rod in Mon. Box |
| | 1981 | LCRC #2270 | Bueche | Set Kent County Monument in Mon. Box |
| | 1994 | LCRC #6917 | Byl | Kent County Monument in Mon. Box |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10/24/81 and was recorded per LCRC #2270.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Bolt he found inside a Mon. Box. Said Bolt checks with Kent Co. Wit. & LCRC #611
LCRC #2270 & #6917

- Nail & KC Remon. tag S. side 24" Oak S70°E 69.90' On old fence N-S
- Nail & KC Remon. tag E. side 10" Maple S10°W 31.51' Btw. N Bd. & S. Bd. US 131
- Nail & KC Remon. tag NW side 8" Ash S50°W 27.93' At N. end N. Bd. ramp off
- Nail & KC Remon. tag S. side 10" Oak N60°W 37.32' Post Rd.
- Nail & KC Remon. tag E. side 15" Maple N10°W 17.05'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-4 Standard Kent County Monument in Mon. Box
- Nail & KC Remon. tag S. side 27" Oak S70°E 69.99'
 - Nail & KC Remon. tag E. side Tw. 12" Maple S10°W 31.41'
 - Nail & KC Remon. tag NW side 10" Ash S50°W 27.83'
 - Nail & KC Remon. tag S. side 12" Oak N60°W 37.23'
 - Nail & KC Remon. tag E. side 15" Maple N10°W 17.05'
 - On old fence N-S Btw. N Bd. & S. Bd. US 131
 - At N. end N. Bd. ramp off Post Rd.



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 2/6/96