

**SURVEY & REMONUMENTATION**

FEB 14 1997

COMMISSION

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**KENT COUNTY**  
(County)

Located In:	Corner Code #
T 8N R 11W	E-6
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Apr. 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6	1837	GLO	Whitcomb	Set Post
		Kent Co. Wit.		1/2" Iron Pipe
	1972	LCRC #228	Spicer	1/2" Iron
	1981	LCRC #2330	Bueche	Set Kent County Monument
	1993	LCRC #6919	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/4/81 and was recorded per LCRC #2330

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found PK Nail at same location per witnesses from above LCRC as set by John C. Bueche in place of the 1/2" Iron over 1" Iron he found. Both Irons check with Kent Co. Wit. and LCRC #228. Set Standard Kent County (Harrison) Monument in place of PK Nail.

LCRC #2330	LCRC #6919
Nail/tag 8" Pine N55°E 37.00'	Nail/tag 8" Pine N60°E 40.60'
Nail/tag 18" Oak S30°E 69.26'	Nail/tag 20" Oak S30°E 69.26'
Nail/tag 26" Oak S20°W 71.02'	Nail/tag 30" Oak S20°W 71.02'
Nail/tag 10" Maple N70°W 37.67'	Nail/tag 15" Maple N70°W 37.68'
	Nail/tag P. Pole N25°W 51.23'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 Standard Kent County Monument	
Set Nail & KC Remon. tag S. side 8" Pine	N60°E 40.92'
Nail & KC Remon. tag W. side 20" Oak	S30°E 69.26'
Nail & KC Remon. tag E. side 30" Oak	S20°W 71.02'
Set Nail & KC Remon. tag N. side 18" Maple	N70°W 37.60'
Nail & KC Remon. tag N. side 20" Oak	S85°E 42.90'
Set Nail & KC Remon. tag NE side P. Pole	N40°W 62.20'
On C/L N-S blacktop; E-W Power Line is N. 40'±	



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 4/26/96

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 JUN -7 AM 8:29  
REG. OF DEEDS

9185

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 5/30/96  
CHAIRMAN John C. Bueche