

SURVEY & REMONUMENTATION

FEB 14 1997 KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey		T <u>8N</u> R <u>11W</u>	<u>E-7</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

REG. OF DEEDS

Handwritten signature

96 MAR 20 AM 8:56

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9054

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN Harry H. H. H.

A. Description of original monument and accessories and/or subsequent restoration:

E-7	1837	GLO	Whitcomb	Set Post
		Kent Co. Wit.		No. desc. - witnesses given
	1972	LCRC #228	Spicer	1" Iron in Mon. Box
	1980	LCRC #1330	Byl	Mon. Box
	1981	LCRC #2331	Bueche	Set Kent County Monument in Mon. Box
	1994	LCRC #6920	Byl	Kent County Monument in Mon. Box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/13/81 and was recorded per LCRC #2331.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Iron he found inside a Mon. Box. Said Iron checks with LCRC #1330. All other witnesses gone
LCRC #2331 & 6920

Top C/L dome C.B.	N73°E	27.45'
Nail & KC Remon. tag E. side 14" Oak	N25°W	74.46'
Nail & KC Remon. tag N. side 8" Poplar	N82°E	62.41'
NE cor. house foundation	S80°W	107.20'
W. edge blacktop W. 13.5'±	C/L blacktop E. (Scott Lake Ct.)	is N. 61'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7	Standard Kent County Monument		
	Top C/L dome C.B.	N73°E	27.49'
	Nail & KC Remon. tag E. side 16" Oak	N25°W	74.43'
	NE cor. house foundation	S80°W	107.28'
	Set Nail & KC Remon. tag N. side 12" Oak	S80°E	53.78'
	W. edge blacktop W. 13.5'±		
	C/L blacktop E. (Scott Lake Ct.)		is N. 61'±



Signed by Kate Breitels

Date 2/6/96

Surveyor's Michigan License No. 30077