

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located In:	Corner Code #
T8N R11W	E-8
T___ R___	_____
T___ R___	_____
T___ R___	_____
T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____
S___ T___ R___	_____

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Apr. 1, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

REG. OF DEEDS

96 JUN -7 AM 8:29

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9186

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Date	Monument	Accessories	Restoration
E-8 1837	GLO	Whitcomb	Set Post
	Kent Co. Wit.		1" Iron
1973	LCRC #452	VanKooten	1" Iron
1980	LCRC #1330	Byl	1" Iron Pipe
1981	LCRC #2332	Bueche	Set Kent County Monument
1994	LCRC #6921	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 5/30/96
CHAIRMAN Harrison Bueche

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/13/81 and was recorded per LCRC #2332

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" x 30" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC's #452 & #1330.

LCRC #2332	LCRC #6921
Nail/tag 10" Poplar N30°W 31.04'	Nail/tag 10" Poplar N30°W 31.02'
Nail/tag Twin 8" Ash N60°W 18.34'	Nail/tag Twin 10" Ash N60°W 18.61'
Nail/tag 18" Oak ?A35°E 26.36'	Nail/tag 18" Oak S30°W 15.53'
Nail/tag 12" Maple N10°E 65.78'	Nail/tag 20" Oak S60°W 29.79'
on N-S fence	Nail/tag 8" Oak S10°E 40.03'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 Standard Kent County Monument

Nail & KC Remon. tag E. side 10" dead Poplar	N30°W	31.02'
Nail & KC Remon. tag N. side Twin 10" Ash	N60°W	18.61'
Nail & KC Remon. tag NW side 20" Oak	S30°W	15.53'
Nail & KC Remon. tag W. side 22" Oak	S60°W	29.79'
Nail & KC Remon. tag W. side 10" Oak	S10°E	40.03'
W'yly face of 8' tall outfield fence post	N50°E	83.93'
On remains N-S fence; C/L old RR grade is N. 200'±		
C/L creek is W. 50'±		



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 4/26/96