

**SURVEY &
REMONUMENTATION KENT COUNTY REMONUMENTATION**

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
KENT COUNTY
(County)

Located In: _____ Corner Code # _____
 1. Public Land Survey T 8N R 11W E-12
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

REG. OF DEEDS
Lucy Spauld
96 MAR 20 AM 8:56
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
9057
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, **Kirk Breitels**, in a field survey on **Jan. 17**, 19 **96** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.
 P.A. 345 1990 KENT COUNTY
 PEER APPROVED *3/7/96*
 CHAIRMAN *Harry Huber*

A. Description of original monument and accessories and/or subsequent restoration:
 E-12 1831 GLO Mullett Set Post
 1940 Kent Co. Wit. Conc. Mon.
 1978 LCRC #1150 Merdzinski 1" Iron
 1990 LCRC #5308 Bueche Set Kent County Monument
 1994 LCRC # Byl Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 6/2/90 and was recorded per LCRC #5308.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 E-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 3/4" x 20" Iron he found. Said Iron checks with LCRC #1150. No witnesses from Kent Co. remain.
LCRC #5308 & #6925
 Nail & KC Remon. tag N. side 6" Pine S80°W 12.90' Iron - East 11.10'
 Nail & KC Remon. tag NE side 24" Oak South 11.20' C/L Woodworth -
 Nail & KC Remon. tag N. side 12" Oak S70°E 27.41' North 33'
 SE cor. brick pillar fence cor. N00°E 67.71' - slope meas.
 SE cor. brick pillar to porch (Hse. #1603) N30°E 89.30' - slope meas.
 The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-12 Standard Kent County Monument
 Nail & KC Remon. tag N. side 6" Pine S80°W 12.90'
 Nail & KC Remon. tag NE side 24" Oak South 11.18'
 Nail & KC Remon. tag N. side 15" Oak S70°E 27.69'
 SE cor. brick pillar fence cor. N00°E 67.71' - slope meas.
 SE cor. brick pillar to porch (Hse. #1603) N30°E 89.24' - slope meas.
 Iron - East 11.10'
 C/L Woodworth - North 33'

Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 2/6/96

