

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey

T 8N R 11W F-1
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:55

REG. OF DEEDS
[Signature]
9058

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Jan. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/1/96
CHAIRMAN *[Signature]*

A. Description of original monument and accessories and/or subsequent restoration:

F-1	1837	GLO	Whitcomb	Not Set
	1903-71	Williams & Works		Stone-Iron-Mon. Box
		Kent Co. Wit.		Mon. Box
	1978	LCRC #1111	Reda	Iron in Mon. Box
	1984	LCRC #4035	Byl	Set Kent County Monument
	1990	LCRC #5672	Marschall	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 11/7/84 and was recorded per LCRC #4035.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl on the Township Line. Said location is 2.2' South of a 1" Iron in a Mon. Box that checks with Williams & Works, Kent Co. Wit. and LCRC #1111.

<u>LCRC #4035</u>				<u>LCRC #5672</u>		
Nail/tag 15" Basswood	S70°W	101.71'	"X" top 24" culv.	S53°W	33.66'	
Nail/tag P. Pole	S00°W	79.60'	"X" top 24" culv.	N53°W	32.96'	
Nail/tag 12" Tw. Cherry	S55°E	51.94'	Nail/tag 42" Oak	S82°W	171.15'	
SE cor. fnd. of house	N60°W	179.25'	Nail/tag 14" Tw. Cherry	S54°E	51.93'	

The selected location is accepted by me and is generally accepted by professional Surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate location of the corner:

F-1 Standard Kent County Monument
 "X" cut on S. end top 24" conc. culv.
 "X" cut on N. end top 24" conc. culv.
 New Nail & KC Remon. tag N. side 50" Oak
 Nail & KC Remon. tag S. side 14" Tw. Cherry
 New Nail & KC Remon. tag S. side 24" Basswood
 SE corner house foundation
 Kent Co. Mon. (F-13, T9N, R11W)

S53°W	33.66'
N53°W	32.96'
S82°W	171.15'
S54°E	51.98'
S70°W	101.53'
N60°W	179.25'
West	372.86'



Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 3/1/96