

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 8N R 11W F-5

T R

T R

T R

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, **Kirk Breittels**, in a field survey on **Jan. 19 19 96** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/7/96

CHAIRMAN [Signature]

A. Description of original monument and accessories and/or subsequent restoration:

F-5	1837	GLO	Whitcomb	Set Post
	1956	Kent Co. Wit.		Iron
	1972	LCRC #285	VanKooten	Iron
	1981	LCRC #2273	Bueche	Set Kent County Monument
	1994	LCRC #6928	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10/16/81 and was recorded per LCRC #2273.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1 1/2" x 24" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #285.

LCRC #2273 & #6928


Nail & KC Remon. tag NE side Tel. Pole	N40°W	47.94'	Nail & KC Remon. tag S. side
Nail & KC Remon. tag N. side 28" Oak	S70°W	87.27'	12" Oak S85°W 14.76'
Nail & KC Remon. tag W. side 14" Oak	S00°W	32.53'	Nail & KC Remon. tag E. side
Nail & KC Remon. tag S. side 10" Oak	S75°E	32.74'	Tw. 8" Oak N25°E 28.33'
Nail & KC Remon. tag SW side CATV Pole	N50°W	49.83'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5 Standard Kent County Monument

Nail & KC Remon. tag S. side 12" Oak	S85°W	14.76'
Nail & KC Remon. tag W. side 18" Oak	S00°W	32.54'
Nail & KC Remon. tag E. side Tw. 8" Oak	N25°E	28.33'
Nail & KC Remon. tag S. side 12" Oak	S75°E	32.77'
Set Nail & KC Remon. tag W. side 15" Oak	N15°W	25.90'
C/L Asph. Rd. N-S is West 33'±		



Signed by

[Signature]

Date

2/6/96

Surveyor's Michigan License No.

30077

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 MAR 20 AM 8:56
REG. OF DEEDS
[Signature]
9060
Register of Deeds Stamp & File Number

