

FEB 14 1997

**KENT COUNTY REMONUMENTATION**

**COMMISSIONER LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**KENT COUNTY**

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>8N</u> R <u>11W</u>	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

96 MAR 20 AM 9:56

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

9061

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 19, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/7/96  
 CHAIRMAN [Signature]

A. Description of original monument and accessories and/or subsequent restoration:

F-7	1837	GLO	Whitcomb	Set Post
	1940	Kent Co. Wit.		Concrete Monument
	1973	LCRC #558	VanKooten	3/4" Iron
	1981	LCRC #2334	Bueche	Set Kent County Monument
	1994	LCRC #6929	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/6/81 and was recorded per LCRC #2334.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 3/4" x 6" Iron on top of a Conc. Mon. he found. Both Iron and Conc. Mon. check with Kent Co. Wit. and LCRC #558.


LCRC #2334 & #6929

Nail & KC Remon. tag SE sid 12" Poplar	S60°W	74.37'	C/L blktp. E-W is S. 1'±
Nail & KC Remon. tag NE side 12" Hickory	S60°E	57.67'	On C/L blktp. N.
Nail & KC Remon. tag NW side Power Pole	N40°E	60.61'	
Nail & KC Remon. tag S. side 30" Maple	N75°E	67.70'	
C/L top of fire hydrant	N50°W	52.16'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 Standard Kent County Monument			
New Nail & KC Remon. tag SE sid 24" Poplar	S60°W	74.31'	
Nail & KC Remon. tag NE side 16" Hickory	S60°E	57.64'	
Nail & KC Remon. tag NW side Power Pole	N40°E	60.61'	
Nail & KC Remon. tag S. side 30" Maple	N75°E	67.70'	
C/L top of fire hydrant	N50°W	52.16'	
C/L blktp. E-W is S. 1'±			
On C/L blktp. N.			



Signed by [Signature]  
 Surveyor's Michigan License No. 30077

Date 2/6/96