

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 MAR 20 AM 8:57
REG. OF DEEDS
Lucy Stand

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T 8N	R 11W	F-9
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

9062

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Jan. 24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96
CHAIRMAN *Henry Huber*

A. Description of original monument and accessories and/or subsequent restoration:

F-9	1831	GLO	Mullett	Set Post
	1933	Kent Co. Wit.		Iron in fence corner
	1977	LCRC #1060	Bonnema	1" Iron
	1981	LCRC #2335	Bueche	Set Kent County Monument
	1994	LCRC #6930	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/13/81 and was recorded per LCRC #2335.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" x 18" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #1060.

<u>LCRC #2335</u>		<u>LCRC #6930</u>	
Nail/tag T. Pole	N70°W 46.13'	Nail/tag T. Pole	N70°W 46.08'
Nail/tag 28" Maple	N90°E 57.48'	Nail/tag 28" Maple	N90°E 57.51'
Nail/tag 8" Poplar	N30°W 14.40'	Nail/tag 10" Oak	S10°W 93.00'
Nail/tag 10" Oak	S10°W 93.05'	Nail/tag 8" Poplar	S45°W 41.40'
PK Nail T. Pole	S30°W 108.58'	PK Nail in T. Pole	S30°W 108.58'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 Standard Kent County Monument

Nail & KC Remon. tag SW side Tele. Pole	N70°W	46.08'
Nail & KC Remon. tag S. side dead 28" Maple	N90°E	57.51'
Nail & KC Remon. tag E. side dead 10" Oak	S10°W	93.00'
Nail & KC Remon. tag SE side 8" Poplar	S45°W	41.40'
PK Nail in S. side Tele. Pole	S30°W	108.58'
Set Nail & KC Remon. tag W. side 8" Basswood	N15°E	61.72'
Set Nail & KC Remon. tag N. side 36" dead Maple	N60°E	142.06'
C/L Tele. Lines N-S is 45'± West		



Signed by *Kirk Breitels*
Surveyor Michigan License No. 30077

Date 2/6/96