

**SURVEY &
REMONUMENTATION**

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>8N</u> R <u>11W</u> | <u>F-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REG. OF DEEDS

Bueche

96 MAR 20 AM 8:57

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9063

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 17, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/2/96

CHAIRMAN *F. J. ...*

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-11	1831	GLO	Mullett	Set Post
	1951	Kent Co. Wit.		Conc. Mon.
	1973	LCRC #560	VanKooten	3/4" Iron
	1981	LCRC #2336	Bueche	Set Kent County Monument
	1994	LCRC #6931	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/6/81 and was recorded per LCRC #2336.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 3/4" x12" Iron and Conc. Mon. he found. Both Iron and Conc. Mon. check with Kent Co. Wit. and LCRC #560.

LCRC #2336 & #6931

Nail & KC Remon.	tag W. side 42" Oak	S15°E	73.95'	C/L School Dr. W. is N. 48'±
Nail & KC Remon.	tag W. side 18" Oak	S40°E	55.97'	C/L N-S blacktop is E. 1'±
Nail & KC Remon.	tag NW side 18" Oak	N65°E	45.00'	
Nail & KC Remon.	tag W. side 16" Oak	N35°E	68.88'	
Top C/L Hydrant		S70°W	23.43'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 Standard Kent County Monument

Nail & KC Remon.	tag W. side 42" Oak	S15°E	73.95'
Nail & KC Remon.	tag W. side 24" Oak	S40°E	55.95'
Nail & KC Remon.	tag NW side 24" Oak	N65°E	44.73'
Nail & KC Remon.	tag W. side 20" Oak	N35°E	68.88'
Top C/L Hydrant		S70°W	23.43'
C/L School Dr. W. is N. 48'±			
C/L N-S blacktop is E. 1'±			



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 2/16/96