

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 MAR 20 AM 8:57

REG. OF DEEDS
Bill Bond

9064

Register of Deeds Stamp & File Number

For corners in **COMMISSION**

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>8N</u> R <u>11W</u> | <u>G-1</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1980 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN *Stan Huber*

	A	B	C	D	E	F	G	H	I	J	K	L	M		
1															
2	6			5			4			3			2	1	
3															
4	7						8			9			10	11	12
5															
6	10						17			16			15	14	13
7															
8	19						20			21			22	23	24
9															
10	30						29			28			27	26	25
11															
12	31						32			33			34	35	36
13															

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|-----|------|---------------|-----------|--------------------------------------|
| G-1 | 1837 | GLO | Whitcomb | Set Post |
| | 1964 | Kent Co. Wit. | | 3/8" Iron in Mon. Box |
| | 1971 | LCRC #92 | Chambers | 3/8" Iron in Mon. Box |
| | 1984 | LCRC #4036 | Byl | Set Kent County Monument in Mon. Box |
| | 1990 | LCRC #5679 | Marschall | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 11/7/84 and was recorded per LCRC #4036

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl on Twp. Line in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with previous measurements and GLO jog. No witnesses available.

- | | | | |
|-------------------|--|-------------------|-----------------------------------|
| <u>LCRC #4036</u> | "X" cut on culv. S25°E 66.25' | <u>LCRC #5679</u> | "X" cut top culv. N31°E 77.12' |
| | "X" cut on culv. N30°E 77.04' | | "X" cut top culv. S28°E 67.30' |
| | C/L "+" of Sta. 8+58 stamped in entrance ramp N20°W 74.72' | | Nail/tag fence post S49°W 122.80' |
| | Nail/tag Fc. Post S50°W 122.85' | | C/L Manhole S78°W 171.91' |
| | | | G-13 West 338.65' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---------------|
| G-1 Standard Kent County Monument | |
| "X" cut on top of N. end 24" conc. culv. | N31°E 77.08' |
| "X" cut on top of S. end 24" conc. culv. | S28°E 67.30' |
| Nail & KC Remon. tag N. side fence cor. post | S49°W 122.80' |
| Centerline of Manhole | S78°W 171.91' |
| "+" of Sta. 8+58 in Hwy. Ramp | N20°W 74.72' |
| Kent Co. Mon. (G-13, T9N, R11W) | West 338.70' |



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/1/96