

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In: #

Corner Code #

1. Public Land Survey	T8N	R11W	G-6
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

REG. OF DEEDS

Eric Standa

96 MAR 20 AM 8:57

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9069

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Jan. 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN Harry Bueche

A. Description of original monument and accessories and/or subsequent restoration:

G-6	1837	GLO	Whitcomb	Set Post
		Kent Co. Wit.		Iron
	1977	LCRC #979	Bonnema	Iron in Mon. Box
	1981	LCRC #2337	Bueche	Set Kent County Monument in Mon. Box
	1987	LCRC #4513	Milliron	Set Kent County Monument
	1994	LCRC #6937	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10/31/81 and was recorded per LCRC #2337.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 Found Kent Co. Mon. (Harrison) per wit. from above LCRC as set by John C. Bueche in place of the 3/4" Iron he found inside a Mon. Box over to of another Iron & Stones. Both check with Kent Co. Wit. & LCRC #979. R. Milliron reset K.C. Mon. same location. LCRC #2337 LCRC #4513 & 6937

Nail/tag 36" Walnut N86°E 84.10'	PK Nail in P.P.	N75°W 24.19'	Nail/tag 27" Maple
Nail/tag C. Elm N32°E 59.52'	C/L top hydrant	S30°W 48.78'	S50°W 44.58'
Nail/tag 24" Maple S48°W 44.55'	PK Nail in P.P.	S80°E 24.03'	SE cor. brk. wing
SE cor. school N70°W 81.29'	Nail/tag 36" Walnut N85°E 83.65'		at SE school cor.
On C/L blktp. N-S	Nail/tag 30" Oak N85°W 60.57'		S60°W 90.66'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 Standard Kent County Monument

Nail & KC Remon. tag N. side P. Pole	N75°W	24.19'
C/L top of fire hydrant	S30°W	48.78'
PK Nail N. side P. Pole	S80°E	24.03'
Nail & KC Remon. tag S. side 36" Walnut	N85°E	83.65'
Nail & KC Remon. tag N. side 30" Oak	N85°W	60.57'
SE cor. brick wing at SE cor. school	S60°W	90.66'



Signed by Kirk Breitels

Date 2/16/96

Surveyor's Michigan License No. 30077