

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T8N R11W	G-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REG. OF DEEDS

95 MAR 20 AM 8:57

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9070

Register of Deeds Stamp & File Number

I, **Kirk Breitels**, in a field survey on **Jan. 19, 1996** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN Harrison

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-7	1837	GLO	Whitcomb	Set Post
	1972	Kent Co. Wit.		"T" Iron
	1972	LCRC #184	Spicer	"T" Iron
	1984	LCRC #3838	Kolehouse	Set Kent County Monument
	1994	LCRC #6938	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 5/13/84 and was recorded per LCRC #3838

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the "T" Iron he found. Said "T" Iron checks with Kent Co. Wit. and LCRC #184.

LCRC #3838 & #6938

Nail & KC Remon. tag NE side T. Pole	S45°E	51.65'	
Nail & KC Remon. tag SW side P. Pole	N45°W	39.80'	C/L MH S45°W 1.86'
Nail & KC Remon. tag SE side P. Pole	S45°W	44.14'	
Face of hydrant at grade	N30°W	44.58'	
SW cor. house foundation (#2415)	N50°E	86.74'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 Standard Kent County Monument

Nail & KC Remon. tag NE side T. Pole	S45°E	51.65'
Nail & KC Remon. tag SW side P. Pole	N45°W	39.80'
Nail & KC Remon. tag SE side P. Pole	S45°W	44.14'
Face of hydrant at grade	N30°W	44.58'
SW cor. house foundation (#2415)	N50°E	86.74'
C/L Manhole	S45°W	1.86'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/6/96