

**SURVEY & REMONUMENTATION**

**KENT COUNTY REMONUMENTATION**

FEB 14 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in

**KENT COUNTY**

(County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	11W	G-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

96 MAR 20 AM 8:57

REG. OF DEEDS

*Lucy St. Paul*

**9071**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 18, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN Randy J. Kolehouse

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

A. Description of original monument and accessories and/or subsequent restoration:

G-8	1837	GLO	Whitcomb	Set Post
	1936	Williams & Works		Iron
	1972	LCRC #184	Spicer	1" Iron
	1984	LCRC #3837	Kolehouse	Set Kent County Monument
	1992	LCRC #6578	Marschall	Set Kent County Monument in Mon. Box
	1994	LCRC #6939	Byl	Kent County Monument in Mon. Box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 5/8/84 and was recorded per LCRC #3837.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Chris Marschall in same location as set in 1984 by Randy J. Kolehouse in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with W & W data and LCRC #184.

LCRC #3837 & (#6939) LCRC #6578 (additional witnesses)

Nail/tag P. Pole	S55°W	57.80'	S. cor. CB	S49°E	49.13'
Nail/tag P. Pole	S60°E	60.16' (73.10')	C/L San. MH	S84°W	19.50'
NW cor. hse. fnd.	S35°E	119.7'	C/L W. River Dr. - North		13.30'
NW cor. CB	S20°W	56.12'			
C/L MH	S80°W	19.55'			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8	Standard Kent County Monument in Mon. Box
Nail & KC Remon. tag SE side P. Pole	S55°W 57.70'
Nail & KC Remon. tag NE side P. Pole	S60°E 73.10'
NW cor. house foundation	S35°E 119.66'
NW cor. Catch Basin	S20°W 56.18'
C/L Manhole	S80°W 19.55'
C/L West River Dr. - North	13'±



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/6/96