

**SURVEY & REMONUMENTATION**

FEB 14 1997

**KENT COUNTY REMONUMENTATION**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>8N</u> R <u>11W</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REC. OF DEEDS

*Lucy Spauld*

96 MAR 20 AM 8:57

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

**9073**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28	●	27		26		25	
11													
12		31		32		33		34		35		36	

I, Kirk Breitels, in a field survey on Jan. 17, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96  
CHAIRMAN Randy J. Kolehouse

A. Description of original monument and accessories and/or subsequent restoration:

G-10	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron
	1984	LCRC #3752	Kolehouse	Set Kent County Monument
	1994	LCRC #6941	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 2/25/84 and was recorded per LCRC #3752

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the Concrete Monument (plat cor.) he found. Said Concrete Monument checks with Kent Co. Wit.  
LCRC #3752 & 6941

Nail & KC Remon.	tag E. side 6" Oak	N10°W	22.85'	On fence to S & W
Nail & KC Remon.	tag N. side 14" Oak	N70°W	16.95'	Fence to E. is N. 3'
Nail & KC Remon.	tag N. side 14" Oak	East	20.70'	Fence to N. is W. 12'
Nail & KC Remon.	tag NE side 12" Oak	S30°E	41.90'	
Nail & KC Remon.	tag W. side 24" Oak	N20°E	36.56'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 Standard Kent County Monument

Nail & KC Remon.	tag E. side 6" Oak	N10°W	22.85'	
Nail & KC Remon.	tag N. side 16" Oak	East	20.70'	
Nail & KC Remon.	tag NE side 14" Oak	S30°E	41.90'	
Nail & KC Remon.	tag W. side 24" Oak	N20°E	36.56'	
Set Nail & KC Remon.	tag W. side 16" Oak	N70°E	16.98'	
On fence to S & W	Fence to E. is N. 3'			Fence to N. is W. 12'



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/6/96