

**SURVEY & REMONUMENTATION**

FEB 14 1997

**KENT COUNTY REMONUMENTATION**

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**KENT COUNTY**

(County)

Located In:

Corner Code #

1. Public Land Survey	T 8N R 11W	G-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REG. OF DEEDS

*Lucy Spauld*

95 MAR 20 AM 8:57

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

**9074**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 17, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN *[Signature]*

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-11	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron - No witnesses
	1972	LCRC #559	VanKooten	"T" Iron
	1981	LCRC #2338	Bueche	Set Kent County Monument
	1994	LCRC #6942	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/13/81 and was recorded per LCRC #2338.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the "T" Iron over a second "T" Iron he found. Both "T" Irons check with LCRC #559.

LCRC #2338 & #6942

PK Nail & washer in curb	N42°W	24.56'
SE screw in Light Post	N85°W	87.37'
SW screw in Light Post	N90°E	74.42'
C/L NE bolt of Loght Post	S50°E	50.55'

On N. curb line of drive & 450'± W. of Plainfield Ave.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 Standard Kent County Monument

PK Nail & washer in curb	N42°W	24.56'
SE screw in Light Post	N85°W	87.37'
SW screw in Light Post	N90°E	74.42'
C/L NE bolt of Loght Post	S50°E	50.55'

On N. curb line of drive & 450'± W. of Plainfield Ave.



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/6/96