

**SURVEY & REMONUMENTATION KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in FEB 14 1997  
KENT COUNTY Located in  
(County)

Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>8N</u> R <u>11W</u> | <u>H-1</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

96 MAR 20 AM 8:57

REG. OF DEEDS

*Lucy Bond*

**9076**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/2/96  
CHAIRMAN Harrison Byl

A. Description of original monument and accessories and/or subsequent restoration:

- |     |         |                  |          |                                      |
|-----|---------|------------------|----------|--------------------------------------|
| H-1 | 1837    | GLO              | Whitcomb | Not Set                              |
|     | 1947-71 | Williams & Works |          | Iron-Mon. Box                        |
|     |         | Kent Co. Wit.    |          | 1/2" Iron in Mon. Box                |
|     | 1971    | LCRC #92         | Chambers | 1" Iron in Mon. Box                  |
|     | 1984    | LCRC #4037       | Byl      | Set Kent County Monument in Mon. Box |
|     | 1994    | LCRC #7071       | Byl      | Kent County Monument                 |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 11/7/84 and was recorded per LCRC #4037.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl on the Township Line in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with Williams & Works, Kent Co. Wit. and LCRC #92.

- LCRC #4037 & #7071
- |   |       |        |                 |
|---|-------|--------|-----------------|
| Nail & KC Remon. tag top of guard rail post | S40°E | 29.40' | H-13, T9N, R11W |
| Nail & KC Remon. tag top of guardrail post  | S40°W | 30.54' | West 251.36'    |
| Nail & KC Remon. tag E. side Power Pole     | N50°W | 63.45' |                 |
| Nail & KC Remon. tag W. side 15" Hickory    | S60°E | 81.58' |                 |
| Iron Pipe with cap                          | N20°E | 42.64' |                 |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-1 Standard Kent County Monument
- |  |       |         |
|--|-------|---------|
| Nail & KC Remon. tag top of guard rail post    | S40°E | 29.40'  |
| Nail & KC Remon. tag top of guard rail post    | S40°W | 30.54'  |
| Set Nail & KC Remon. tag E. side (new) P. Pole | N50°W | 62.65'  |
| Nail & KC Remon. tag SW side 15" Hickory       | S60°E | 81.58'  |
| Iron Pipe with cap                             | N20°E | 42.64'  |
| Kent Co. Mon. (H-13, T9N, R11W)                | West  | 251.38' |



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 3/2/96