

FEB 14 1997

KENT COUNTY REMONUMENTATION

**COMMISSIONER LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**KENT COUNTY**  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>8N</u>	R	<u>11W</u>	<u>H-10</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Section	S		T		
	S		T		

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
96 MAR 20 AM 8:57  
REG. OF DEEDS  
*Lucy Spand*

**9080**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Jan. 15, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

H-10	1831	GLO		Not Set	P.A. 345 1990 KENT COUNTY
	1973	Kent Co. Wit.		PEER APPROVED <u>3/7/96</u>	
	1975	LCRC #836	Bonnema	Iron at 24" Oak	CHAIRMAN <u>Harry Huber</u>
	1992	LCRC #6577	Marschall	Iron at E. side 24" Oak	
				1/2" Iron imbedded in the East base of a 34" Oak	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Chris Marschall on 10/9/92 and was recorded per LCRC #6577.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H-10 Found 1/2" Iron Pipe imbedded in the East base of a 34" Oak per witnesses from above LCRC as set by Chris Marschall in place of the he found. Said checks with Kent Co. Wit.

LCRC #6577

Nail & KC Remon. tag NW side 16" Sassafras (15° list)	N60°E	11.42'
Face of a 30" Oak	N45°W	10'±
Nail & KC Remon. tag NW side 14" Sassafras	N20°E	17.30'
Nail & KC Remon. tag NW side 18" Oak (5' high)	N30°E	45.29'
Nail & KC Remon. tag SE side 14" Oak (5' high)	N15°W	24.14'
Face of a 30" Oak	N90°W	21'±
Nail & KC Remon. tag NE side 28" Oak	S30°E	64.25'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-10 1/2" Iron Pipe imbedded in the East base of a 34" Oak		
Nail & KC Remon. tag NW side 16" Sassafras (15° list)	N60°E	11.42'
Face of a 30" Oak	N45°W	10'±
Nail & KC Remon. tag NW side 14" Sassafras	N20°E	17.30'
Nail & KC Remon. tag SE side 14" Oak (5' high)	N15°W	24.14'
Face of a 30" Oak	N90°W	21'±
Nail & KC Remon. tag NE side 28" Oak	S30°E	64.25'



Signed by *Kirk Breitels*

Date 2/6/96

Surveyor's Michigan License No. 30077