

KENT COUNTY REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	11W	H-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

REG. OF DEEDS

David Bond

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 MAR 20 AM 8:57

9082

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **Kirk Breitels**, in a field survey on **Jan. 15**, 19 **96**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1831	GLO	Mullet	Set Post	P.A. 345 1990 KENT COUNTY
	1937	Kent Co. Wit.		Boat Spike in 1" Iron	PEER APPROVED <i>3/17/96</i>
	1975	LCRC #842	Chambers	"T" Iron	<i>Harrison</i>
	1981	LCRC #1790	Merdzinski	Set Kent County Monument	
	1988	LCRC #4849	Bueche	Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/23/81 and was recorded per LCRC #1790.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 6" Iron over an 18" "T" Iron he found. Both Irons check with LCRC #842. No witnesses from Kent Co. remain.
LCRC #1790 & 4849

Nail & KC Remon. tag E. side 40" Oak	N00°E	26.72'
Nail & KC Remon. tag W. side 15" Pine	N35°E	43.32'
Nail & KC Remon. tag NW side MBT & CTV Pole	N55°E	51.39'
Nail & KC Remon. tag NE side P. Pole	S70°E	82.31'
Nail & KC Remon. tag SE side 20" Oak	S65°W	41.28'
NW cor. stone garage #2790	S30°W	100.83'
SE cor. frame garage	N40°W	102.68'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Standard Kent County Monument

New Nail & KC Remon. tag E. side 48" Oak	N00°E	26.92'
New Nail & KC Remon. tag W. side 15" Pine	N35°E	43.27'
Nail & KC Remon. tag NW side CATV Pole	N55°E	51.32'
Nail & KC Remon. tag NE side P. Pole	S70°E	82.50'
New Nail & KC Remon. tag SE side 24" Oak	S65°W	41.08'
NW cor. stone garage #2790	S30°W	100.72'
SE cor. frame garage	N40°W	102.7'
Kent Co. Mon. (H-1, T7N, R11W)	East	57.03'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. **30077**

Date **2/6/96**