

FEB 14 1997

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

Lucy Standa

96 MAR 20 AM 8:58

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey		T 8N R 11W	I-1
		T ___ R ___	_____
		T ___ R ___	_____
		T ___ R ___	_____
2. Property Controlling in Section	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____

9083

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breiteis, in a field survey on Jan. 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96

CHAIRMAN *Harrison Byl*

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-1	1837	GLO	Whitcomb	Set Post
	1879-1966	Williams & Works		Leaded Stone-Mon. Box
	1970	Kent Co. Wit.		Iron in Mon. Box
	1984	LCRC #4038	Byl	Set Kent County Monument in Mon. Box
	1994	LCRC #7072	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 11/7/84 and was recorded per LCRC #4038.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl on Twp. Line in place of the 1" Iron over another 1" Iron he found inside a Mon. box. Both Irons check with Williams & Works information and Kent Co. Wit.

<u>LCRC #4038</u>		<u>LCRC #7072</u>	
Nail/tag P. Pole	S10°E 75.10'	Nail/tag P. Pole	S10°E 75.10'
Nail/tag 12" Walnut	S05°E 88.71'	Nail/tag 15" Walnut	S05°W 88.71'
1" Iron Pipe	N00°E 45.40'	Nail/tag 12" Poplar	S35°W 71.04'
1" Iron Pipe	N45°E 63.93'	PK Nail in curb joint	N55°E 42.31'
KC Mon.-SW 35-9-11	N90°W 202.02'	KC Mon. SW 35-9-11	N90°W 202.02'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Standard Kent County Monument		
Nail & KC Remon. tag E. side P. Pole	S10°E	75.10'
Nail & KC Remon. tag W. side 15" Walnut	S05°W	88.71'
PK Nail & KC Remon. tag in curb joint	N55°E	42.31'
Kent Co. Mon. (I-13, T9N, R11W)	N90°W	202.03'



Signed by *Kirk Breiteis*
Surveyor's Michigan License No. 30077

Date 3/2/96