

FEB 14 1997

**KENT COUNTY REMONUMENTATION**

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**KENT COUNTY**

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>8N</u> R <u>11W</u>	<u>I-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

95 MAR 20 AM 8:58

REG. OF DEEDS

**9084**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 29, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3	●	2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/7/96  
CHAIRMAN Harry Muehler

A. Description of original monument and accessories and/or subsequent restoration:

I-2	1837	GLO	Whitcomb	Set Post
	1879-1962	Williams & Works		Leaded Stone
		Kent Co. Wit.		Leaded Stone
	1990	LCRC #5310	Bueche	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 2/13/90 and was recorded per LCRC #5310.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Leaded Stone he found. Said Stone checks with Williams & Works information and Kent Co. Wit.

LCRC #5310

Nail & KC Remon. tag N. side 24" Oak	S80°W	8.08'
Nail & KC Remon. tag W. side 10" Oak	S10°E	26.32'
Nail & KC Remon. tag N. side 26" Oak	S80°E	37.95'
Nail & KC Remon. tag E. side P. Pole (#157-158)	North	71.23'
Nail & KC Remon. tag NW side 22" Oak	S60°W	41.40'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2 Standard Kent County Monument

New Nail & KC Remon. tag N. side 24" Oak	S80°W	8.10'
New Nail & KC Remon. tag W. side 12" Oak	S10°E	26.36'
New Nail & KC Remon. tag N. side 30" Oak	S80°E	37.95'
Nail & KC Remon. tag E. side P. Pole (#30)	N00°E	71.26'
New Nail & KC Remon. tag NW side 24" Oak	S60°W	41.45'

Corner is on N. woods line and S. of Power Lines E-W



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/6/96