

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
KENT COUNTY
(County)

Located In:

Corner Code #

- | | | | | | |
|--------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey | T | 8N | R | 11W | I-6 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 MAR 20 AM 8:58
REG. OF DEEDS
David J. Stand

9088

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

I, **Kirk Breitels**, in a field survey on **Jan. 16**, 19**96**,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | | |
|-----|------|---------------|-----------|---------------------------------------|-----------------------------|
| I-6 | 1837 | GLO | Whitcomb | Set Post | P.A. 345 1990 KENT COUNTY |
| | 1972 | Kent Co. Wit. | | Iron | PEER APPROVED 3/7/96 |
| | 1983 | LCRC #3234 | Bonnema | 1/2" Iron | CHAIRMAN <i>[Signature]</i> |
| | 1983 | LCRC #3532 | Stadt | Set Kent County Monument | |
| | 1988 | LCRC #4853 | Bueche | Kent County Monument | |
| | 1991 | LCRC #6196 | Brintnall | Set Kent County Monument after const. | |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russel E. Stadt on 9/7/83 and was recorded per LCRC #3532.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Arthur W. Brintnall at the same location as set by Russel E. Stadt in place of the 1/2" Iron over a Concrete Monument he found. Both Iron and Conc. Monument check with Kent Co. Wit. and LCRC #3234.

LCRC #3532 & #4853 & #6196

- | | | | |
|-------------------------------------------|-------|--------|-------------------|
| Nail & KC Remon. tag NW side 12" Tri. Oak | S45°W | 31.85' | |
| Nail & KC Remon. tag N. side 14" Oak | N65°W | 19.34' | C/L N-S Asph. Rd. |
| Nail & KC Remon. tag NE side 20" Oak | N25°W | 41.47' | (Packer Dr.) is |
| Nail & KC Remon. tag NW side 22" Oak | N30°E | 47.61' | East 1.5'± |
| Nail & KC Remon. tag S. side 22" Oak | N70°E | 29.69' | |
| NW cor. brick garage (house #6390) | S80°E | 87.76' | |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-6 Standard Kent County Monument
- | | | |
|-----------------------------------------------|-------|--------|
| New Nail & KC Remon. tag NW side 12" Tri. Oak | S45°W | 31.85' |
| Nail & KC Remon. tag N. side 16" Oak | N65°W | 19.34' |
| New Nail & KC Remon. tag NE side 24" Oak | N25°W | 41.45' |
| Nail & KC Remon. tag NW side 27" Oak | N30°E | 47.63' |
| New Nail & KC Remon. tag S. side 27" Oak | N70°E | 29.70' |
| NW cor. brick garage (house #6390) | S80°E | 87.80' |
- C/L asphalt road N & S (Packer Dr.) is East 1.5'±



Signed by *[Signature]*
Surveyor's Michigan License No. **30077**

Date **2/6/96**