

**SURVEY & REMONUMENTATION**

**KENT COUNTY REMONUMENTATION**

FEB 14 1997

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**  
**KENT COUNTY**  
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	11W	I-12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 MAR 20 AM 8:58  
 REG. OF DEEDS  
*[Signature]*

**9094**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Jan. 15, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-12 1831 GLO	Mullet	Set Post
Kent Co. Wit.		Leaded Stone
1973 LCRC #596	Spicer	1/2" Iron Pipe
1981 LCRC #2384	Bueche	Set Kent County Monument
1988 LCRC #4859	Bueche	Kent County Monument
1993 LCRC 36742	Roon	Set Kent County Monument (after const.)

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/2/96  
 CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/18/81 and was recorded per LCRC #2384.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1/2" x 24" Solid Iron he found. Said Solid Iron checks with Kent Co. Wit. and LCRC #596.

LCRC #6742

"X" cut SW cor. catch basin frame	N40°E	52.18'	All witnesses from LCRC's #2384 & #4859 were removed during construction
"X" cut SE cor. catch basin frame	N05°W	49.97'	
Spike in top of guard rail post	N80°W	8.80'	
PK Nail in top of guard rail post	S25°W	17.43'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-12 Standard Kent County Monument

"X" cut SW cor. catch basin frame	N40°E	58.18'
"X" cut SE cor. catch basin frame	N05°W	50.03'
Spike in top of guard rail post	N80°W	8.80'
PK Nail in top of guard rail post	S25°W	17.45'
C/L S. bound lane of E. Beltline is East 15.5'±		



Signed by *[Signature]*  
 Surveyor's Michigan License No. 30077

Date 2/6/96