

**KENT COUNTY REMONUMENTATION**

FEB 14 1997

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
KENT COUNTY  
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>8N</u>	R	<u>11W</u>	<u>I-13</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 MAR 20 AM 8:58  
 REG. OF DEEDS  
*Lucy Bond*  
**9095**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 15, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

I-13	1831	GLO	Mullet	Set Post
		Kent Co. Wit.		3/4" Iron on Leaded Stone
1974	LCRC #692	Bonnema		3/4" Iron
1978	LCRC #1191	Merdzinski		Set PK Nail from previous witnesses
1981	LCRC #1788	Merdzinski		Set Kent County Monument
1988	LCRC #4860	Bueche		Kent County Monument
1991	LCRC #6739	Roon		Reset Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1/23/81 and was recorded per LCRC #1788

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Russel L. Roon at the same location as set by John A. Merdzinski in place of the PK Nail & 1 1/2" x 18" Iron he found. Said PK Nail & Iron checks with Kent Co. Wit. and LCRC #1191.

<u>LCRC #1788 &amp; 4860</u>		<u>LCRC #6739</u>	
Nail/tag 38" Oak	S40°W 100.73'	Nail/tag P. Pole	N60°W 72.09'
Nail/tag 28" Maple	S70°W 60.37'	Nail/tag 40" Oak	S40°W 100.30'
Nail/tag P. Pole	N40°W 38.10'	E'ly cor. conc. base	N35°W 72.15'
Nail/tag P. Pole	N70°E 71.13'	Cast Iron Mon.	East 62.22'
Nail/tag 16" Hickory	S35°E 108.88'		
Kent Co. Mon.	East 62.22'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-13 Standard Kent County Monument

Nail & MDOT tag SW side Power Pole	N60°W	72.09'
Nail & MDOT tag E. side 40" Oak	S35°W	100.30'
E'ly cor. conc. base Guy Pole	N35°W	72.15'
NW cor. conc. base. Guy Pole	S50°E	62.74'
Kent Co. Mon. (I-1 T7N, R11W)	East	62.22'

Mon. is just West of S. bound E. Beltline and on C/L 4 Mile Rd. ±.



Signed by *Kirk Breitels*

Date 2/6/96

Surveyor's Michigan License No. 30077