

**SURVEY & REMONUMENTATION**

FEB 14 1997

COMMISSION

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey		T <u>8N</u> R <u>11W</u>	<u>J-1</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

REG. OF DEEDS

*Lucy [Signature]*

96 SEP 13 PM 12:03

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

**9344**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on July 29 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	

P.A. 345 1990 KENT COUNTY

PEER APPROVED 8/22/96  
CHAIRMAN Harry Kubel

A. Description of original monument and accessories and/or subsequent restoration:

J-1	1837	GLO	Whitcomb	Not Set
	1879-1971	Williams & Works		Leaded Stone-Mon. Box
	1970	Kent Co. Wit.		1" Iron in Mon. Box
	1971	LCRC #73	Spicer	Iron in Mon. Box
	1984	LCRC #4039	Byl	Set Kent County Monument in Mon. Box
	1994	LCRC #7073	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 11/7/84 and was recorded per LCRC #4039.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl on Twp. Line in place of the 3/4" Iron Pipe over a 1" Iron Pipe he found inside a Mon. Box. Both Irons check with Williams & Works, Kent Co. Wit. and LCRC #73 LCRC #4039 & 7073

Capped Iron	S00°W	60.03'
Iron Pipe	S00°W	39.83'
NW cor. Sec. 2-8-11 (Kent Co. Mon.)	S90°W	2614.33'
NE cor. Sec. 2-8-11 (Kent Co. Mon.)	N90°E	2614.99'
Kent Co. Mon. (J-13, T9N, R11W)	S90°W	156.65'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Standard Kent County Monument		
Capped Iron	S00°W	60.03'
Iron Pipe	S00°W	39.83'
NW cor. Sec. 2-8-11 (Kent Co. Mon.)	S90°W	2614.17'
NE cor. Sec. 2-8-11 (Kent Co. Mon.)	N90°E	2615.16'
Kent Co. Mon. (J-13, T9N, R11W)	S90°W	156.65'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 8/25/96