

**SURVEY & REMONUMENTATION**  
 FEB 14 1997  
 COMMISSION

**KENT COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 SEP 13 PM 12:05  
 REG. OF DEEDS  
*Lucy Spard*

For corners in KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T8N R11W	J-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**9360**  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Kirk Breitels, in a field survey on Aug. 23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 J-12 1837---GLO---Not Set 1963---Williams & Works---Found Leaded Stone  
 ---Kent Co. Wit.---3/4" Iron (same wits. as LCRC #690)  
 1974---LCRC #690---Bonnema---3/4" Iron "checks comp. int. 1/4 lines"  
 Leaded Stone SSE 6.64' 6" Oak SW 11.07' E-W fence 7' South  
 18" Oak SE 15.86' 12" Sassafras NNE 13.04' P.A. 345 1990 KENT COUNTY  
 1991---LCRC #5727---G. Ford---3/4" Iron  
 Leaded Stone SSE 6.64' 12" Sassafras NNE 13.16' PEER APPROVED 8/22/96  
 24" Oak SE 15.99' 6" Oak NW 16.13' CHAIRMAN *Harry Staker*  
 1993---Research---Chettleburgh---Used per Exxel survey (LCRC #690)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 J-12 Found 3/4" Iron Pipe per the following witnesses:  
 Leaded Stone SSE 6.70' 15" Sassafras NNE 13.2'  
 24" Oak SE 16.0' 9" Oak NW 16.1' 10" Oak WSW 11.1'

Said 3/4" Iron Pipe is 0.3' S. and 0.3' W. from intersection of 1/4 lines and agrees with survey measurements of others. "Summer Meadows" - plat by Nederveld & Assoc. - has Center of Sec. 35-8-11 per LCRC #5727.

The 3/4" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-12 Set Standard Kent County Monument in place of 3/4" Iron Pipe
- Set Nail & KC Remon. tag E. side 15" Sassafras N30°E 13.25'
- Set Nail & KC Remon. tag S. side 24" Oak S60°E 16.02'
- Set Nail & KC Remon. tag S. side 9" Oak N45°W 16.06'
- Set Nail & KC Remon. tag NW side 10" Oak S65°W 11.13'
- Leaded Stone - SSE 6.70'



Signed by *Kirk Breitels*  
 Surveyor's Michigan License No. 30077

Date 9/4/96