

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In: Corner Code #

1. Public Land Survey	T <u>8N</u> R <u>11W</u>	<u>K-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REG. OF DEEDS

Handwritten signature

96 JUN -7 AM 8:29

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9192

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Apr. 1, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-3	1837	GLO	Whitcomb	Set Post
	1938	Kent Co. Wit.		Leaded Stone
	1979	LCRC #1252	Merdzinski	Leaded Stone
	1981	LCRC #2322	Merdzinski	Set Kent County Monument
	1988	LCRC #4866	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 5/30/96
CHAIRMAN *Handwritten signature*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 11/2/81 and was recorded per LCRC #2322

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski over top of the Leaded Stone he found. Said Leaded Stone checks with Kent Co. Wit. and LCRC #1252.

<u>LCRC #2322</u>	<u>LCRC #4866</u>
Nail/tag 10" Oak N70°W 31.16'	Nail/tag 12" Oak N70°W 31.2'
Nail/tag 14" Oak S50°E 35.90'	Nail/tag 16" Oak S50°E 35.90'
Nail/tag 14" Oak N70°E 34.34'	Nail/tag 16" Oak N70°E 34.34'
Nail/tag 12" Oak N10°E 53.21'	Nail/tag 14" Oak N10°E 53.10'
Fence West is North 22.8'±	Nail 8" Oak S00°E 3.17'


The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 Standard Kent County Monument

Nail & KC Remon. tag NW side 12" Oak	N70°W	31.30'
New Nail & KC Remon. tag NE side 18" Oak	S50°E	35.84'
New Nail & KC Remon. tag S. side 18" Oak	N70°E	34.58'
New Nail & KC Remon. tag W. side 16" Oak	N10°E	53.13'
Nail in E. side 8" Oak	S00°E	3.17'

On old fence N-S; Fence to West is North 22.8'±



Signed by *Handwritten signature*
Surveyor's Michigan License No. 30077

Date 4/26/96