

SURVEY & REMONUMENTATION

**REMONU
KENT COUNTY REMONUMENTATION**

FEB 14 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>8N</u>	R	<u>11W</u>	<u>K-8</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

REG. OF DEEDS

W. J. Bond

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
96 MAR 20 AM 8:59

9107

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Jan. 16, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8	1837	GLO	Whitcomb	Set Post
		Kent Co. Wit.		Iron
	1976	LCRC #965	Bonnema	3/4" Iron
	1981	LCRC #2379	Bueche	Set Kent County Monument
	1988	LCRC #4871	Bueche	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/18/81 and was recorded per LCRC #2379.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 3/4" x 18" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC #965.

LCRC #2379 & #4871

Nail & KC Remon. tag E. side 20"	Pine	S25°W	76.10'
Nail & KC Remon. tag NW side 18"	Pine	S50°W	84.23'
Nail & KC Remon. tag N. side 30"	Oak	S65°W	58.55'
Nail & KC Remon. tag E. side 30"	Oak	S35°W	41.90'
Nail & KC Remon. tag N. side 12"	Pine	N80°W	28.94'
Face of 6" dia. steel post		N80°E	29.00'

C/L bit. N-S is E. 3'±, Bt. Spike N. 5.15' & S. 24.79'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8	Standard Kent County Monument
New Nail & KC Remon. tag E. side 20"	Pine S25°W 76.13'
New Nail & KC Remon. tag NW side 18"	Pine S50°W 84.23'
New Nail & KC Remon. tag E. side 36"	Oak S35°W 41.90'
New Nail & KC Remon. tag N. side 14"	Pine N80°W 28.96'
Face of 6" dia. steel post	N80°E 29.04'
C/L bit. N-S is E. 3'±, Fence to W. is N. 4'±	

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/7/96
CHAIRMAN Harry Bueche



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/6/96