

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>8N</u> R <u>11W</u> | <u>K-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 96 MAR 20 AM 8:59
 REG. OF DEEDS
W. J. [Signature]
9114
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-12	1831	GLO	Mullett	Set Post
		Kent Co. Wit.		Leaded Stone
	1974	LCRC #692	Bonnema	Stone
	1980	LCRC #1443	Merdzinski	Set Kent County Monument
	1988	LCRC #4874	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/7/96
 CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10/22/80 and was recorded per LCRC #1443

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Leaded Stone he found. Said Stone checks with Kent Co. Wit. and LCRC #692

LCRC #1443 & #4874

Nail/tag 12" Oak	S09°E	27.85'	Nail/tag 15" Oak	N10°E	8.87'
Nail/tag 10" Oak	S50°W	26.91'	SW'ly face fence post	N50°E	4.34'
Nail/tag Tri. 16" Oak	S70°W	91.04'	Iron - West		40.10'
Nail/tag 10" Oak	S40°E	46.66'	Fence cor.		3.5'± N. & 2.5'± E.
Nail/tag 8" Oak	S72°E	49.30'			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 Standard Kent County Monument

New Nail & KC Remon. tag W. side 15" Oak	S09°E	27.89'
New Nail & KC Remon. tag S. side 14" Oak	S65°W	26.86'
New Nail & KC Remon. tag N. side Tri. 24" Oak	S80°W	91.74'
New Nail & KC Remon. tag E. side Tw. 14" Oak	S40°E	46.63'
New Nail & KC Remon. tag N. side 12" Oak	S72°E	49.34'
New Nail & KC Remon. tag E. side 20" Oak	N10°W	8.86'
Iron Pipe - West		40.15'



Signed by *[Signature]*
 Surveyor's Michigan License No. 30077

Date 2/6/96