

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

FEB 14 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>11W</u>	<u>L-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REG. OF DEEDS

[Signature]

9115

Register of Deeds Stamp & File Number

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

96 MAR 20 AM 8:59

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 25, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/21/96
CHAIRMAN [Signature]

A. Description of original monument and accessories and/or subsequent restoration:

L-1	1837	GLO	Whitcomb	Not Set
	1899-1967	Williams & Works		Fence Post-Iron-Mon. Box
	1967	Kent Co. Wit.		1" Iron
	1975	Survey	Kistler & Assoc.	1" Iron
	1984	LCRC #4041	Byl	Set Kent County Monument
	1994	LCRC #7075	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 11/7/84 and was recorded per LCRC #4041.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl on Township line 0.88' South of Mon. Box he found. Said location checks with Williams & Works and Kistler & Assoc. information. No witnesses remain.

LCRC #4041

C/L SE bolt, E. end of S. handrail, E. end of bridge	S75°W	156.80'
C/L NE bolt, E. end of N. handrail, E. end of bridge	N80°W	167.80'
"X" cut in C/L E-W walk	N00°E	27.81'
"X" cut in C/L E-W walk	S00°W	39.76'
Kent Co. Mon. (L-13, T9N, R11W)	S90°W	35.04'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 Standard Kent County Monument		
C/L SE bolt, E. end of S. handrail, E. end of bridge	S75°W	156.80'
C/L NE bolt, E. end of N. handrail, E. end of bridge	N80°W	167.80'
"X" cut in C/L E-W walk	S00°W	39.76'
Nail & KC Remon. tag top of guard rail post	N00°E	32.01'
Kent Co. Mon. (L-13, T9N, R11W)	S90°W	35.04'
Iron in Mon. Box is North 0.88'		



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/6/96