

SURVEY & REMONUMENTATION

FEB 14 1997

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>8N</u> R <u>11W</u>	<u>L-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REG. OF DEEDS

Lucy Bond

96 JUN -7 AM 8:29

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9196

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Apr. 1, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-11	1831	GLO	Mullett	Set Post
	1951	Kent Co. Wit.		Iron
	1981	LCRC #2066	Nederveld	Iron
	1982	LCRC #3118	Merdzinski	Set Kent County Monument
	1988	LCRC #4880	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 5/30/96
CHAIRMAN Gary Thupree

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10/12/81 and was recorded per LCRC #3118

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 3/4" Iron he found. Said 3/4" Iron checks with LCRC #2066. No Kent Co. Wit. remain.

LCRC #3118			LCRC #4880		
SE cor. garage	N50°W	81.90'	SE cor. garage #4635	N50°W	81.90'
Nail/tag 12" Oak	S50°E	66.90'	Nail/tag 14" Oak	S50°E	67.08'
Nail/tag 12" Oak	S15°E	54.28'	Nail/tag 14" Oak	S15°E	54.36'
Nail/tag fence post	S88°W	25.00'	Nail/tag fence post	S88°W	25.00'
Conc. Mon.	South	14.63'	Nail/tag 6" Poplar	South	41.81'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Standard Kent County Monument	
SE cor. garage #4635 (siding)	N50°W 81.90'
New Nail & KC Remon. tag N. side 18" Oak	S50°E 66.90'
New Nail & KC Remon. tag E. side 18" Oak	S15°E 54.29'
New Nail & KC Remon. tag E. side 8" Poplar	South 41.81'
Set Nail & KC Remon. tag S. side wood fc. post	S60°W 26.58'
Mon. is at South end of gravel drive	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 4/26/96