

FEB 14 1997

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|--------------|---------------|-------------|
| 1. Public Land Survey | T <u>8</u> N | R <u>11</u> W | <u>L-12</u> |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

REG. OF DEEDS

Lucy J. Bond

96 SEP 13 PM 12:06

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9362

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Aug. 23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- L-12 1837---GLO---Not Set
 1908---Williams & Works---Intersection of fences, 2630' East of W 1/4 cor.
 1954---Williams & Works---Same as 1908 per notes
 1990---Survey---Exxel Eng.---3/4" Iron Pipe
 Quad. 14" Cherry SW 12.99' 18" Oak NW 14.36' P.A. 345 1990 KENT COUNTY
 18" Cherry N 31.83' 18" Oak E 68.70' PEER APPROVED 8/22/96
 Fence cor. for fences W & S is 12' W. and 4' N. CHAIRMAN *Harry Huber*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-12 Found 3/4" Iron Pipe per the following witnesses:
 PK in 24" Oak WNW 14.36' Fc. to S. is 12'± W.
 PK in 24" Cherry N 31.86' Fc. to W. is 4'± N.
 PK in Quad. 24" Cherry SW 12.94'
 PK in 30" Oak E 68.6'

Said 3/4" Iron Pipe is 1.3' E. and less the 0.1' S. from intersection of 1/4 lines and agrees with survey measurements of others.

The 3/4" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-12 Set Standard Kent County Monument in place of the 3/4" Iron Pipe
 Set Nail & KC Remon. tag N. side Quad 18" Cherry S60°W 13.25'
 Set Nail & KC Remon. tag N. side 24" Oak N60°W 14.32'
 Set Nail & KC Remon. tag W. side 24" Cherry N00°W 31.85'
 Set Nail & KC Remon. tag N. side 30" Oak S80°E 68.85'
 Fence to South is 12'± West
 Fence to West is 4'± North



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 9/4/96