

**SURVEY & REMONUMENTATION**

**KENT COUNTY REMONUMENTATION**

FEB 14 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<b>KENT COUNTY</b> (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 11W	<u>M-3</u>
	<del>T 8N R 10W</del>	<del>A 5</del>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

96 MAR 20 AM 8:59

REG. OF DEEDS

*Lucy Bond*

**9120**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 22 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

P.A. 315 1990 KENT COUNTY  
PEER APPROVED 3/7/96  
CHAIRMAN Harry Huber

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-3	1837	GLO	Brookfield	Set Post
	1960	Kent Co. Wit.		1/2" Oblong Bar
	1979	LCRC #1374	VanKooten	1/2" Oblong Bar next to jagged Stone
	1982	LCRC #3115	Merdzinski	Set Kent County Monument
	1988	LCRC #4883	Bueche	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10/23/82 and was recorded per LCRC #3115

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" x 1/2" Iron next to a Slate Stone he found. Both Iron and Stone check with Kent Co. Wit. and LCRC #1374.  
LCRC #3115 & #4883

Nail & KC Remon. tag W. side 10" Elm	N35°E	7.63'
Nail & KC Remon. tag W. side 10" Elm	N30°W	23.52'
Nail & KC Remon. tag N. side 6" Oak	N65°E	17.88'
Nail & KC Remon. tag E. side 15" W. Cherry	S20°E	36.89'
Nail & KC Remon. tag NW side 30" Maple	S25°W	15.49'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 Standard Kent County Monument

New Nail & KC Remon. tag W. side 12" Elm	N35°E	7.57'
New Nail & KC Remon. tag W. side 12" Elm	N30°W	23.58'
New Nail & KC Remon. tag N. side 12" Oak	N65°E	17.87'
Nail & KC Remon. tag E. side 20" W. Cherry	S20°E	36.94'
Nail & KC Remon. tag NW side 32" Maple	S25°W	15.51'

Monument is on N-S Hwy. R/W fence W. side Northland Dr.



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 2/6/96