

**SURVEY & REMONUMENTATION**

FEB 14 1997 KENT COUNTY REMONUMENTATION

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**KENT COUNTY**

(County)

Located In:

Corner Code #

1. Public Land Survey

T 8N R 11W

M-7

~~T 8N R 10W~~

~~A-7~~

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 22, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		"T" Iron on Mon.
1973		LCRC #459	Spicer	"T" Iron
1981		LCRC #1978	Jonker	Set Kent County Monument in Mon. Box
1988		LCRC #4887	Bueche	Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/8/96

CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8/20/81 and was recorded per LCRC #1978.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the "T" Iron he found inside a Mon. Box. Said "T" Iron checks with Kent Co. Wit. and LCRC #459.

LCRC #1978 & #4887

Nail & KC Remon. tag N. side T. Pole	S75°W	65.87'
Nail & KC Remon. tag SW side 30" Tw. Chestnut	N28°W	68.83'
Nail & KC Remon. tag W. side T. Pole	N20°E	75.0'
NW cor. garage foundation	S25°E	96.71'
Face of steel fence post	S07°W	25.52'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate localizing the position of the corner:

M-7 Standard Kent County Monument

Nail & KC Remon. tag N. side T. Pole	S75°W	65.93'
New Nail & KC Remon. tag SW side 32" Tw. Chestnut	N28°W	68.66'
Nail & KC Remon. tag W. side T. Pole	N20°E	75.00'
NW cor. garage foundation	S25°E	96.76'
Face of steel fence post	S07°W	25.52'
On C/L bit. E-W & N		



STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 96 MAR 20 AM 8:59  
 REG. OF DEEDS  
*Lucy Stand*

**9124**

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/6/96