

\$7.00
\$2.00

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>8N</u> R <u>11W</u> | <u>K-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>leg. 2</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REG. OF DEEDS

Luci St. Paul

38 DEC 23 AM 8:59

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

11075

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Oct. 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	19		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K-1 Kent County Monument, LCRC #9101, 3/2/96
- | | | |
|---|-------|---------|
| Nail & KC Remon. tag S. side P. Pole | S60°W | 59.24' |
| Nail & KC Remon. tag N. side Guy Pole | N60°W | 59.71' |
| Nail & KC Remon. tag S. side P. Pole | S60°E | 52.71' |
| NW cor. conc. porch slab of house | S30°E | 88.26' |
| SE cor. conc. porch foundation of house | N50°E | 133.30' |
| SW cor. Sec. 36-9-11 (Kent Co. Mon.) | N90°W | 109.09' |

P.A. 345 1990 KENT COUNTY,
PEER APPROVED 3/7/96
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-1 Found BROKEN Kent Co. Monument per above witnesses. Removed and reset Kent Co. Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1 Standard Kent County Monument
- | | | |
|---|-------|---------|
| Nail & KC Remon. tag S. side P. Pole | S60°W | 59.24' |
| Nail & KC Remon. tag N. side Guy Pole | N60°W | 59.71' |
| Nail & KC Remon. tag S. side P. Pole | S60°E | 52.76' |
| NW cor. conc. porch slab of house | S30°E | 88.26' |
| SE cor. conc. porch foundation of house | N50°E | 133.30' |
| SW cor. Sec. 36-9-11 (Kent Co. Mon.) | N90°W | 109.09' |



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 12/15/98