

**\$7.00**  
**\$2.00** SEP 18 1995  
**COMMISSION**

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**KENT COUNTY**

	Located In:	Corner Code #
1. Public Land Survey	T 8N R 12W	A-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUN 29 AM 11:50  
REG. OF DEEDS  
*Luci Stand*

**8417**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-1	1837	GLO	Brookfield	Set Post
	1951	Williams & Works		Iron
	1965-70	Williams & Works		Iron in mon. box
	1973	Kent Co. Wit.		Mon. Box
	1984	LCRC #4081	Kolehouse	Set Kent County Monument in mon. box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/10/84 and was recorded per LCRC #4081

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 3/4" Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit. and Williams & Works information.

LCRC #4081

Nail & KC Remon. tag NW side P. Pole	N50°E	69.38'
Nail & KC Remon. tag NE side 8" Pine	N45°W	76.08'
Top C/L MBT Riser	S45°E	53.15'
Top C/L MBT Riser	S45°W	54.40'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/95  
CHAIRMAN *Randy Kolehouse*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-1 Standard Kent County Monument

Nail & KC Remon. tag NW side P. Pole	N50°E	69.38'
Nail & KC Remon. tag W. side P. Pole	N15°W	123.53'
Top C/L MBT Riser	S45°E	53.15'
Top C/L MBT Riser	S45°W	54.30'
"X" cut top conc. culv.	S55°E	78.84'
"X" cut top conc. culv.	S35°W	73.20'



Signed by *Kirk Breitels* Date 6/22/95  
Surveyor's Michigan License No. 30077