

\$7.00
\$2.00
SEP 18 1995
COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	A-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 JUN 29 AM 11:50
REG. OF DEEDS
8419

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Feb. 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-4	1837	GLO	Brookfield	Set Post
	1935	Kent Co. Wit.		Conc. Mon.
	1984	LCRC #4319	Bueche	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/2/84 and was recorded per LCRC #4319.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the conc. mon. he found. Said conc. mon. checks with Kent Co. Wit.

LCRC #4319

KC Remon. tag & nail E. side dbl. 16" Ash	S40°W	49.00'
KC Remon. tag & nail N. side 12" Maple	N50°W	27.42'
KC Remon. tag & nail SW side 10" Walnut	N30°W	47.27'
KC Remon. tag & nail W. side 12" W. Cherry	N30°E	50.47'
KC Remon. tag & nail N. side 14" Walnut	N80°E	27.93'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 6/22/95
CHAIRMAN Harry Bueche

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 Standard Kent County Monument

KC Remon. tag & nail E. side dbl. 22" Ash	S40°W	46.58'	(other branch of 1981)
OC Remon. tag & nail N. side 15" Maple	N50°W	27.40'	
KC Remon. tag & nail SW side 15" Walnut	N30°W	47.27'	
OC Remon. tag & nail W. side 15" W. Cherry	N30°E	50.18'	
KC Remon. tag & nail N. side 14" Walnut	N80°E	27.86'	

Common with M-4, T8N, R13W, Ottawa Co.



Signed by Kirk Breitels

Date 6/22/95

Surveyor's Michigan License No. 30077