


on this certificate.

Surveyor's Michigan License No. \_

## KENT COUNTY REMONUMENTATION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY		Filing Requirement of Act 74, Mich. P.A. 197		1970	,
	(County)	Located In:	Corner Code ##	DEED AM READER	
1.	Public Land Survey	T R 12W T R T R T R	A-7	S 2 = S S S S S S S S S S S S S S S S S	
2.	Property Controlling in Section	S T R S T R		8422	
3.	Miscellaneous Property in Sec.	S T R S T R		Register of Deeds Stamp & File Number	r 
				ABCDEFGHIJK	L M
5.	Private Claims				
	•			3	_i_
				4 7 8 9 10 11	_  12
1	Kirk Breitels	in a field survey on	April 395	, 5	
in !	hereby certify that under r lines 1 and 2 above were	requirements of P.A. 74, Michigan P.A. in conformance with regulations a	A. of 1970, the corner points mentioned and rules therefore as required in the artment of the Interior, Bureau of Land	e	3
Ma abo	inagement or by a decree of ove were in conformance v	of a Court of Law and/or that the corn with the rules of the Michigan Board	ner points mentioned in lines 3, 4 and 5 of Land Surveyors or by a Decree of a -monumented, recovered, found as	5 8 19 20 21 22 23 a	-24-
expressed below:				10 30 29 20 27 26	<b>—25</b> —
NC	TE: Not more than 4	corners, all in the same town a	and range, may be recorded	11	



A-7	1837	GLO	Brookfield	Set Post	
		Ottawa Co. Wit.		Sleigh shoe	
	1986	LCRC #4407	Bueche	Set Kent County Monument	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John c. Bueche on 3/11/85 and was recorded per LCRC #4407.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Rerod he found. Said Rerod checks with previous survey data by others and testimony of property owner as to the location of corner.

LCRC #4407

PK Nail in top of fence post S20°E 4.19'
Nail E. side 12" Box Elder S20°E 29.10'
Nail E. side 10" Box Elder S40°E 56.58'
Nail S. side 8" Maple S80°E 42.18'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6 /22 / 9 - S
CHAIRMAN

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1	Standard Kent County Mondment			
	PK Nail in top of fence post	S20°E	4.60' (1	eaning S'ly)
	Set Nail & KC Remon. tag E. side 16" Box Elder	-S20°E	29.01'	33300010000
	Set Nail & KC Remon. tag E. side 14" Box Elder	S40°E	56.64'	OF MICH
	Set Nail & KC Remon. tag S. side 12" Box Elder	S80°E	42.06'	1
	C/L ditch to NW & E is N 6' m/l			KIRK
				BREITELS
				LAND **
				SURVEYOR
				NO CONT
				30077
		,	/ / -	A Comment of the same
Signed by _	/ Culs 1 Munts Da	te 6	122/95	LAND S STEET
,5, _	30077	•	,	. and the transfer of the same

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28. 1971 Revised May 14. 1975 Revised Jan.. 1983