

SEP 18 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	A-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 95 AUG 29 AM 10:38
 REG. OF DEEDS
Lucy S. ...

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Aug. 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: P.A. 345 1990 KENT COUNTY
 A-9 1837 GLO Brookfield Set Post PEER APPROVED 8/24/95
 1959 Kent Co. Wit. 1" Iron CHAIRMAN *[Signature]*
 1975 LCRC #813 Bonnema Pinched Iron
 1982 LCRC #3199 Nederveld Found Ottawa Co. Monument in mon. box
 1993 Bueche Witness Ottawa Co. Mon. prior to constr.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, as found by Gordon D. Nederveld on 11/15/82 and was recorded per LCRC #3199.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A-9 DID NOT FIND ANYTHING AT THE ROAD SURFACE. Set standard Kent Co. Mon. (Harrison) over remains of Ottawa Co. Mon. per witnesses from above LCRC and 1993 J. Bueche wit. in the same location as Ottawa Co. Mon. found by Gordon D. Nederveld. Said Ottawa Co. Mon. checks with Kent Co. Wit. and LCRC #813

LCRC #3199	Bueche 1993
N & T E. side 22" Maple N10°W 90.05'	NE cor. hse. fnd. N25°W 148.71'
SE corner porch fnd. N45°W 128.90'	SW cor. hse. fnd. N60°W 180.49'
N & T NW side 20" Maple N60°E 63.20'	N & T S. side P. Pole N75°W 184.43'
PK top conc. ROW marker S48°W 44.40'	N & T SE side P. Pole S70°W 190.64'
N & T SW side P. Pole S63°E 94.34'	N & T NW side 10" Maple N50°E 96.70'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-9 Standard Kent County Monument
 NE cor. house foundation N25°W 148.71'
 SW cor. house foundation N60°W 180.49'
 Nail & KC Remon. tag S. side P. Pole N75°W 184.43'
 Nail & KC Remon. tag SE side P. Pole S70°W 190.64'
 Nail & KC Remon. tag NW side 10" Maple N50°E 96.70'
 Set Nail & KC Remon. tag NE side P. Pole S60°E 99.75'
 C/L "X" of bit. roads E-W, gravel S.



Signed by *Kirk Breitels*

Date 8/24/95

Surveyor's Michigan License No. 30077