

\$7.00 SEP 18 1995
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	A-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

REG. OF DEEDS

Handwritten signature

95 JUN 29 AM 11:51

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8425

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on March 8, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11	1837	GLO	Brookfield	Set Post
	1885	Williams & Works		Stone
	1935	Kent Co. Wit.		Stone
	1976	Ottawa Co. Wit.		Cast Iron Mon.
	1984	LCRC #4168	Bueche	Found Ottawa Co. Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, recorded by John C. Bueche on 10/27/84 and was recorded per LCRC #4168

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11 Found standard Ottawa Co. Mon. (Harrison) per witnesses from above LCRC as recorded by John C. Bueche. Said Ottawa Co. Mon. checks with Kent Co. Wit. and Ottawa Co. Wit. LCRC #4168

KC Remon. tag & Nail side fence post	N50°E	47.19'
KC Remon. tag & Nail E. side fence post	S15°E	30.27'
Nail in N. side P. Pole	S60°E	116.40'
"X" cut on S. end conc. pipe	S70°E	101.62'
"X" cut on N. end conc. pipe	N80°E	102.05'
Nail in W. side 4" Cherry on C/L gravel road W., blacktop E., gravel N.	N30°E	68.10'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/22/95
CHAIRMAN *Handwritten signature*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Standard Ottawa County Monument		
KC Remon. tag & Nail S. side fence post	N50°E	47.19'
OC Remon. tag & Nail E. side fence post	S15°E	30.79'
Nail in N. side P. Pole	S60°E	116.40'
"X" cut on S. end conc. pipe	S70°E	101.62'
"X" cut on N. end conc. pipe	N80°E	102.05'
OC Remon. tag & Nail in W. side 6" Cherry on C/L gravel road W., blacktop E., gravel N.	N30°E	68.12'



Signed by *Kirk Breitels* Date 6/22/95

Surveyor's Michigan License No. 30077