

\$7.00
\$2.00

SEP 18 1935

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T	<u>8N</u>	R	<u>12W</u>	<u>B-1</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 JUN 29 AM 11:51
REG. OF DEEDS
Lucy Standa

8427
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on April 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1	1837	GLO	Not Set
	1951	Kent Co. Wit.	1" Iron
	1984	LCRC #4082	Set Kent County Monument in mon. box
	1991	LCRC #6110	Kent County Monument in mon. box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/16/84 and was recorded per LCRC #4082

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set on Twp. line by Randy J. Kolehouse in place of the 1" iron he found inside a mon. box. Said Iron checks with Kent Co. Wit.

LCRC #4082 & #6110

Nail & KC Remon. tag W. side elec. serv. pole	S30°E	40.71'	
SW cor. barn fnd.	N10°W	32.13'	
SE cor. barn fnd.	N35°E	41.42'	
NE cor. brick gar. (Hse. #4422)	S30°W	115.74'	
SE cor. pole barn (wood fnd.)	N10°W	128.86'	
KC Mon. at S 1/4 cor. Sec. 31, T9N, R12W	West	307.15'	

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/22/95
CHAIRMAN *Randy Kolehouse*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 Standard Kent County Monument in mon. box

Nail & KC Remon. tag W. side elec. serv. pole	S30°E	40.71'
SW cor. barn fnd.	N10°W	32.13'
SE cor. barn fnd.	N35°E	41.42'
NE cor. brick gar. (Hse. #4422)	S30°W	115.74'
SE cor. pole barn (wood fnd.)	N10°W	128.86'
KC Mon. at S 1/4 cor. Sec. 31, T9N, R12W	West	307.10'



Signed by *Kirk Breitels*

Date 6/22/95

Surveyor's Michigan License No. 30077