

\$7.00 SEP 18 1995  
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 12W	C-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUN 29 AM 11:51  
REG. OF DEEDS  
8432

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kirk Breitels, in a field survey on March 2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1 1837 GLO Brookfield Set Post  
Kent Co. Wit. 1" Iron in mon. box  
1984 LCRC #4083 Kolehuse Set Kent County Monument in mon. box  
1991 LCRC #6111 Byl Reset Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehuse on 11/16/84 and was recorded per LCRC #4083

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl at the same position as set in 1984 on the twp. line by Randy J. Kolehuse in place of the Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit.

LCRC #6111  
SW cor. conc. project marker N10°W 46.82'  
Nail & KC Remon. tag SE side P. Pole N55°E 75.95'  
Nail & KC Remon. tag NE side Guy Pole S65°E 70.53'  
Nail & KC Remon. tag W. side Guy Pole S30°E 48.11'  
Nail & KC Remon. tag W. side Lt. Pole N10°W 34.33'  
KC Mon. at SE cor. Sec. 31, T9N, R12W West 305.30'

P.A. 345 1900 KENT COUNTY

PEER APPROVED 6/22/95  
CHAIRMAN *[Signature]*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 Standard Kent County Monument  
SW cor. conc. project marker N10°W 46.82'  
Nail & KC Remon. tag SE side P. Pole N55°E 75.95'  
Nail & KC Remon. tag NE side Guy Pole S65°E 71.93' (different pole)  
Nail & KC Remon. tag W. side Guy Pole S30°E 48.11'  
Nail & KC Remon. tag W. side Lt. Pole N10°W 34.33'  
KC Mon. at SE cor. Sec. 31, T9N, R12W West 305.30'

Signed by *[Signature]*  
Surveyor's Michigan License No. 30077

Date 6/22/95

