

SEP 18 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	C-6
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 95 AUG 29 AM 10:39
 REG. OF DEEDS
W. J. [Signature]
 8690

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Aug. 1, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6	1838	GLO	Whitcomb	Set Post
	1939	Kent Co. Wit.		Conc. Mon.
	1972	Kent Co. Wit.		1" Iron
	1977	LCRC #1227	Byl	1" Iron Pipe in Mon. Box
	1981	LCRC #2395	Bueche	Set Kent County Monument in mon. box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/10/81 and was recorded per LCRC #2395.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" Pipe (Conc. Mon.) he found inside a mon. box. Said checks with Kent Co. Wit. and LCRC #1227.

LCRC #2395

- Nail & KC Remon. tag SW side P. Pole S15°E 173.50'
- Nail & KC Remon. tag NW side P. Pole N35°E 84.52'
- Nail & KC Remon. tag SW side 8" Apple N60°W 100.08'
- Nail & KC Remon. tag W. side 8" Apple N35°W 90.03'
- C/L Blktp. N-S is East 2' m/l; on field division West

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 8/24/95
 CHAIRMAN [Signature]

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 Standard Kent County Monument

- Nail & KC Remon. tag SW side P. Pole S15°E 173.50'
- Nail & KC Remon. tag NW side P. Pole N35°E 84.60'
- New Nail & KC Remon. tag SW side 12" Apple N60°W 99.90'
- New Nail & KC Remon. tag W. side 12" Apple N35°W 89.98'
- C/L Blktp. N-S is East 2' m/l; on field division West



Signed by [Signature]

Date 8/24/95

Surveyor's Michigan License No. 30077