

\$7.00  
\$2.00

SEP 18 1995  
COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>12W</u>	<u>C-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 JUN 29 AM 11:51  
REG. OF DEEDS  
*Lucy Bond*

8434

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 7, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-11	1838	GLO	Whitcomb	Set Post
	1959	Kent Co. Wit.		Conc. Mon.
	1976	LCRC #934	Bonnema	Square Spike
	1981	LCRC #2397	Bueche	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/31/81 and was recorded per LCRC #2397

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Square Spike inside a Conc. Mon. he found. Said Spike and Conc. Mon. checks with Kent Co. Wit. and LCRC #934.

LCRC #2397

NW cor. conc. headwall	S54°E	120.22'
KC Remon. tag & nail E. side 30" Pine	S35°W	61.04'
KC Remon. tag & nail N. side 26" Pine	S68°W	90.93'
KC Remon. tag & nail E. side 24" Maple	N17°W	61.40'
KC Remon. tag & nail W. side 20" Walnut	N20°E	94.11'
C/L blacktop N-S is East 110' m/l on C/L blktp. E-W		

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/95  
CHAIRMAN Harry Huber

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Standard Kent County Monument

NW cor. conc. headwall	S54°E	120.22'
New KC Remon. tag & nail E. side 32" Pine	S35°W	61.01'
New KC Remon. tag & nail N. side 28" Pine	S68°W	90.98'
New KC Remon. tag & nail E. side 26" Maple	N17°W	61.43'
New KC Remon. tag & nail W. side 22" Walnut	N20°E	94.14'
C/L blacktop N-S is East 110' m/l On C/L blktp. E-W		



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 6/22/95