

SURVEY & RECONSTRUCTION

JAN 24 1996

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	D-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 DEC 20 AM 8:37  
REG. OF DEEDS  
*Lucy Bond*

8770

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Oct. 23, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-4 1837 GLO Not Set
- 1991 Survey Fricke Intersection 1/4 lines-set capped rerod
- 1991 Survey Nederveld & Assoc. Intersection of 1/4 lines-no point set

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/26/95  
CHAIRMAN Harry Huber


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-4 Found Capped Rerod (Fricke) 1.6' E. & 0.5' S. of intersection of 1/4 lines. Chuck Fricke told me he set the Center of Section 8 at "intersection of 1/4 lines." 1/4 line measurements and angles from 1991 Nederveld & Assoc. survey agree with the intersection of 1/4 lines as computed by us ±. Intersection of 1/4 lines falls on field/woods division to North and West ±.

The intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-4 Set Standard Kent County Monument at the intersection of 1/4 lines.
- Set Nail & KC Remon. tag S. side 12" Elm S90°W 4.52'
- Set Nail & KC Remon. tag E. side 10" Elm N35°W 22.19'
- Set Nail & KC Remon. tag W. side 30" Oak N00°E 37.59'
- Set Nail & KC Remon. tag S. side 32" Maple S80°E 51.33'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 12/6/95