

\$7.00 SEP 18 1995  
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY

	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>12W</u>	D-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REG. OF DEEDS

*Lucy Bond*  
8439

95 JUN 29 AM 11:52

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, Kirk Breitels, in a field survey on Feb. 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5	1838	GLO	Whitcomb	Set Post
		Kent Co. Wit.		Conc. Mon.
	1977	LCRC #1229	Byl	Set 3/4" Iron over Conc. Mon.
	1981	LCRC #2399	Bueche	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/10/81 and was recorded per LCRC #2399

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John c. Bueche in place of the 3/4" Iron over a Conc. Mon. he found. Said Iron and Conc. Mon. check with Kent Co. Wit. and LCRC #1229.

LCRC #2399

KC Remon. tag & nail NW side 6" Apple	S45°W	53.10'
KC Remon. tag & nail W. side 10" Apple	S40°E	36.80'
KC Remon. tag & nail NE side 10" Apple	S65°E	89.22'
C/L 3" Gas Line Marker (East Marker)	N80°W	131.54'
C/L 2" Apple (No tag or nail)	N30°E	49.85'

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 6/22/95  
CHAIRMAN Harry Huber

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 Standard Kent County Monument		
New KC Remon. tag & nail NW side 8" Apple	S45°W	53.22'
New KC Remon. tag & nail W. side 12" Apple	S40°E	36.82'
New KC Remon. tag & nail NE side 12" Apple	S65°E	89.24'
C/L 3" Gas Line Marker (East Marker)	N80°W	131.54'
Set KC Remon. tag & nail E. side 6" Apple	N30°E	49.89'
C/L blktp. E-W is North 3' m/l on field division North		



Signed by Kirk Breitels  
30077

Date 6/22/95

Surveyor's Michigan License No. \_\_\_\_\_