

SUBJECT
 \$7.00
 \$2.00
 SEP 18 1985
 COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>12W</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 95 JUN 29 AM 11:52
 REG. OF DEEDS
Lucy Spauld
 8444
 Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 15, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-3	1838	GLO	Whitcomb	Set Post
	1899	Williams & Works		Leaded Stone
	1935	Kent Co. Wit.		Conc. Mon.
	1969	Williams & Works		PK - Iron
	1985	LCRC #4329	Bueche	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10/17/85 and was recorded per LCRC #4329.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the "T" Iron he found over a Stone. Both "T" Iron and Stone check with Kent Co. Wit. and Williams & Works information.

LCRC #4329

KC Remon. tag & nail E. side Power Pole	S65°W	70.55'
KC Remon. tag & nail W. side Serv. Pole	S15°E	53.40'
KC Remon. tag & nail N. side 24" Walnut	S65°E	81.81'
KC Remon. tag & nail NW side 6" Apple	N50°E	58.21'
Face of 2" Apple	N55°W	73.11'

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 6/22/95
 CHAIRMAN *Harry Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3 Standard Kent County Monument

KC Remon. tag & nail E. side Power Pole	S65°W	70.63'
PK Nail W. side Service Pole	S15°E	53.36'
New KC Remon. tag & nail N. side 24" Walnut	S65°E	81.75'
New KC Remon. tag & nail NW side 10" Apple	N50°E	58.07'
Set KC Remon. tag & nail S. side 6" Apple	N55°W	73.18'



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 6/22/95