

SEP 18 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T	8N	R	12W	E-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

REG. OF DEEDS

8445

95 JUN 29 AM 11:52

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on April 24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-4	1838	GLO	Whitcomb	Set Post
	1935	Kent Co. Wit.		Conc. Mon.
	1977	LCRC #1089	VanKooten	1" Iron
	1981	LCRC #2403	Bueche	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 11/9/81 and was recorded per LCRC #2403.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 Found Boat Spike over remains of standard Kent Co. (Harrison) Mon. (16" below road) per witnesses from above LCRC as set by John C. Bueche in place of the 1" x 18" Iron he found. Said Iron checks with LCRC #1099.

LCRC #2403

"X" cut on South end of conc. culv.	S80°W	58.75'
"X" cut on North end of conc. culv.	N78°W	59.32'
KC Remon. tag & nail E. side 8" Poplar	S30°W	144.70'
KC Remon. tag & nail W. side 8" Pine on field division East & West	S10°E	136.63'
C/L blktp. N & S is 1.5' m/l West		

P.A. 315 1970 KENT COUNTY

PEER APPROVED 6/22/95  
CHAIRMAN [Signature]

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 Replaced Boat Spike with Standard Kent County Monument over remains of old monument

"X" cut on North end of conc. culv.	N78°W	59.32'
"X" cut on North end of conc. culv.	N90°E	55.90'
Set Nail & KC Remon. tag SE side 15" Pine	S60°W	240.37'
Set Nail & KC Remon. tag W. side 16" Poplar on field division East & West	S10°E	169.19'
on C/L blktp. N & S		



Signed by [Signature]

Date 6/22/95

Surveyor's Michigan License No. 30077